MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- जोन-01 अंतर्गत वाय शेप ब्रिज में लगे ट्यूबलर पोल का संधारण कार्य।

(As Per PWD ElectricalSOR 01.07.2015)

| S.No. | Description and details of work | Qty. | Unit |
|-------|--|-------|------|
| 1 | Supplying and laying following sizes one number PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. 4 x 25 sq. mm. | Metre | 200 |
| 2 | Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as required. 30x20x15 cms. | 45.00 | Each |

Executive Engineer Municipal Corporation Bhilai (C.G) Asstt. Engineer Municipal Corporation Bhilai (C.G)

Sub. Engineer Municipal Corporatio Bhilai (C.G)