

MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :- वॉलीबल ग्राउण्ड निर्माण कार्य सेक्टर 02 भिलाई नगर जिला दुर्ग।

S.N.	Description and details of work	As Per Building SOR 01.01.2015 & Non Sor Item	
		Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. (In all types of soils.)	3.51	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.41	cum
3	providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	4.8	sqm
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	14.52	cum
5	Providing and laying nominal mix Reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 40mm nominal size).	2.65	cum
6	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	87.21	KG
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	132.38	KG
8	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	210.00	KG
9	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, base of columns and plinth beam in any shape and size.	15.00	Sqm
10	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	31.50	Sqm
11	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	15.00	Sqm
12	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	14.40	Cum
13	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	96.00	Sqm Cum
14	NON SOR ITEM :- Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass. Captivating design Vivacious colors Beautiful pattern	112.00	sqm
15	NON SOR ITEM :- LED MODULE 300watts (2year warranty) housing, black silver (bajab, haveli etc.) AC90-350V, 50/60HZ, PFC>0.95, 100-135LM/W CRI>75, 2700-6500K, IP67, 427X305X122mm	6.00	sqm NO'S

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई