

NAGAR NIGAM BHILAI**NIT****CONSTRUCTION OF DOME SHED AT WARD 26 NEAR KALIBADI MANDIR****(AS PER PWD BUILDING S.O.R 01.01.2015)**

S.NO	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other ... the excavated area), including dressing and leveling of pits. In all types of soils.	38.88	Cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor...and watering, including dressing etc. complete.	5.18	Cum
3	Providing and laying nominal mix reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	12.11	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars FE 415	1211.40	Kg
5	Structural steel work riveted or bolted or welded ... cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	8121.20	Kg
6	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	438.00	Sqm
7	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	12.80	Sqm
8	Painting on new work (two or more coats) to give an even shade with: Aluminium paint	655.34	Sqm

**ASSTT.ENGINEER****Nagar Palik Nigam, Bhilai****SUB ENGINEER****Nagar Palik Nigam, Bhilai**