MUNICIPAL CORPORATION OF BHILAI

DETAILED ESTIMATE

वार्ड क्र0-47 सेक्टर-01 इस्पात भवन का विस्तारीकरण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.07.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 100 mm diameter	100	Meter
2	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm2 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	2.00	No.
3	Cement concrete flooring with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20mm) finished with a floatingcoat of neat cement, 40 mm thick	50.00	Sqm
4	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design:100 mm diameter S.W. pipe	80.00	Meter
5	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	174.96	Kg
6	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	20.00	КG
7	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	10.00	Kg
8	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS: 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion etc complete. 110 mm dia	10.00	Mtr
9	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS: 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion etc complete 150 mm dia	10.00	Mtr
	Neat Cement punning.	100.00	Sqm
	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	0.67	Cun
- 1	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead. Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement: 3 fine	2.00	Eacl
<u> </u>	and)	100.24	Sqn
<u> </u>	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:In Cement Mortar 1:5 (1 cement: 5 fine sand)	96.00	Sqr
ſ	Providing and making 12mm thick cement plaster of mix:In Cement Mortar 1:4 (1 cement : 4 ine sand)	180.00	Sqı
5 0	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. :4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	10.56	Cu
7 r	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, noulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler naterial throughout the hollow panel, casted monolithically with testing parameters of F.R.P. aminate conforming to table - 3 of IS: 14856: 2000, complete.	3.60	Cu

he

Trula

S.N.	PARTICULERS OF ITEMS	Quantity	UOM	1
18	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	1.00	Each	ı
	class designation 4.0 in foundation and plinth in:	8.81	Cum	1
20	rioriting and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement: 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement: 3 coarse sand) but excluding reinforcement.	0.60	Cun	n
21	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	35.09	Cur	m
22	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	842.80	K	g
23	concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement ; 2 coarse sand ; 4 graded store assets to 1.	10.06	Cu	ım
24	water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white	00.00	So	ļm
25	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size	50.00) So	qm
26	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, shades and 12 mm thick bed of cement Mortar 1:3cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	30.0	0 s	qm
27	Distempering with acrylic washable distemper to give an even shade. On oldwork (two or more coats)	1 190.	00 S	Sqn
28	washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10	150.	00 8	Sqr
29	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS: 723 with all fittings and fixtures complete. White	1, 2		Eac
30	paint Saint Synthetic enamel		65	Sq
31	intings complete. 32 mm dia	1 2	00	Ea
32	and floors wherever required: White Orissa pattern W.C. pan of size 580x440 mm		.00	Ea
33	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS: 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required: White pedestal type	g 1	.00	E

Jan .

Ruth

S.N	PARTICULERS OF ITEMS	Quantity	UOM
34	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required: White Size 550 450	2.00	Each
35	Towel rail (600mm long x 20mm dia)	4.00	Each
36	Chequerred precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand): Ordinary cement without any pigment	2.25	Sqm
37	Water Supply Sanitary Work , Electrification Work Lum-Sum	1 1 1	
38	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	3.60	Cum
39	Executation for all types and the sizes of foundation, trenches and drains or for any other purpose including dressing and leveling of pits. In all types of spil.	52.11	Cum
40	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: a)Foundations, footings; base of columns and plinth because any charge and rice.	66.80	Sqm
41	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	11.27	Sqm
42	Carriage by mechanical transport for 5 km lead.	8.64	Cum
43	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel	26.05	sqm
44	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and	300.00	Sqm
45	lead upto 50m (at least 5m away from the dressed area). Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½	4.80	Cum
46 3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 605 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 6 mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping one complete of minimum compressive strength of 250 kg/sq.cm	300.00	Sqm
47 B	roviding and fixing form work including centring, shuttering, strutting, staging, propping racing etc. complete and including its removal at all levels, for:Columns, Pillars, Piers and likesectangular or square in shape	9.60	Sqm
48 bi	roviding and fixing form work including centring, shuttering, strutting, staging, propping racing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access leafners, balconies (plain surfaces) and shelves (cast in situ)	10.24	Sqm
49 br	roviding and fixing form work including centring, shuttering, strutting, staging, propping acing etc. complete and including its removal at all levels, for: Beams, lintels, cantilevers &	16.00	Sqm
Br cla suj	rick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of ass designation 4.0 in foundation and plinth in: Cement Mortar 1:6 + Extra for brick work in perstructure above plinth level for every floor or part thereof in addition to rate for foundation designation designation.	10.57	Cum
Pro we	oviding and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars lded to steel frame of windows etc. including applying a priming coat welded to frame with necessary fitting complete including applying a priming of red oxide zinc chromate primer.	72.00	Kg
2 con	nting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of etc. pplete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including ning coat of exterior primer applied @ 2.20 kg/ 10 sqm)	36.00	Sqm
Dis	tempering with acrylic washable distemper to give an even shade. On new work (Two or e coats)	36.00	Sqm

Ju

Franka

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
54	Painting on new work (two or more coats) to give an even shade with Satin synthetic enamel	120.00	Sqm
55	Coment concrete flooring with coment concrete 1:2-4 (1 coment : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating cost of next coment.50 mm thick	9.00	Sqm

कार्यपालन व्यक्तियन्ता नगर पालिक निगम, भिलाई सहायक अभियन्ता नगर पातिक निगम, मिलाई भिलाई

चप अभियन्ता नगर पालिक निगम,