MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :- पार्षद निधि से कृपाल नगर में नाली निर्माण एवं सड़क निर्माण कार्य।

Pwd Building & Road Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Providing and laying Cement Concrete for plain concrete/reinforced concrete i/c form work, shuttering copmlete in as per drawings and specifications. (For Village roads) P.C.C.M25	13.05	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	16.36	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	2.73	Cum
4	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	5.76	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	460.56	KG
6	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: a)Foundations, footings; base of columns and plinth beam in any shape and size	48.48	Sqm
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	0.26	Cum
8	Carriage by mechanical transport for 5 km lead.	16.36	Cum

Executive Engineer Municipal Corporation Bhilai (C.G)

Asstt. Engineer Municipal Corporation Bhilai (C.G) Sub. Engineer
Municipal Corporatio
Bhilai (C.G)