



NAGAR PALIK NIGAM BHILAI**NIT**

वार्ड क्र.-27 हाउसिंग बोर्ड में एम.आई.जी. 182 एवं एल.आई.जी. 752 के सामने सीवर लाईन संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	Qty	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soil	63.00	Cum
2	Dismantling of old S.W. pipes including breaking of joints and bed concrete stacking of useful materials near the site within 50 m lead but beyond 20m and disposal of unserviceable materials:		
	200 mm diameter	100.00	mtr.
3	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the roportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :		
	200 mm diameter	114.00	mtr.
4	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.		
		42.00	Cum
5	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)		
		45.76	sqm
6	Neat Cement punning.		
		45.76	sqm
			
	ASSTT.ENGINEER		
	Nagar Palik Nigam, Bhilai		
			
		SUB ENGINEER	
		Nagar Palik Nigam, Bhilai	