


MUNICIPAL CORPORATION BHILAI (C.G.)


nit

Name of work :- अवकाश - 04 अक्टूबर - 31 व 32 में नैतिक एवं
सुव्यवस्था निर्माण कार्य

As per Building SOR

S.No.	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	121.54	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	57.82	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. <i>PCC 1:1 1/2:3</i>	3.776	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm <i>Pigment Coloured</i>	519.2	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	108.56	cum


Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)


Sub Engineer
Municipal Corporation
Bhilai (C.G.)