MUNICIPAL CORPORATION OF BHILAI

वार्ड क्र. 38 ठेठवार यादव समाज हेतु एक सामाजिक भवन निर्माण कार्य।

ומא מא מא מא מו שו צו מו שו שו

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.0

S.N.	(As Per PWD Building SOR 01.01.2015 & PARTICULERS OF ITEMS	ž.	01.06.2020
		Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	37.60	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	9.46	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:15:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	26.138	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars	2613.8	Kg
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	38.28	Sqm
(B)	Columns, Pillars, Piers and likes- rectangular or square in shape	39.60	Sqm
(C)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	101.52	Sqm
(D)	Beams, lintels, cantilevers & walls	13.92	Sqm
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	14.40	Cum
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	9.55	Cum
8	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	54.72	Sqm
9	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	124.00	Sqm
	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	109.20	Sqm
11	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	414.00	Kg
12	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	320.40	Sqm

			UCM
S.N.	PARTICULERS OF ITEMS	Quantity	COIM
13	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm Thick	54.00	Sqm
14	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	109.2	Sqm
15	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	178.72	Sqm
16	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	29.76	Sqm
17	Add Extra For Electrification Work (As Per Electric SOR 01.06.2020)	23839.00	LS

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer

Municipal Corporation

Bhilai