

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड 47 सेक्टर 01 सड़क 04 खेल मैदान में चैनलिंग फेसिंग एवं लाईट संधारण कार्य।

As Per PWD Building SOR 01.01.2015 & Electrical SOR 1.6.2020,

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	8.946	Cum
2	Providing and laying nominal mix Reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 40mm nominal size).	14.826	Cum
3	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	432.259	Kg
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.52	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	741.3	Kg
6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	733.152	Kg
7	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, base of columns and plinth beam in any shape and size.	84.00	sqm
8	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	126.00	sqm
9	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	84.00	sqm
	Electrical SOR 1.6.2020		
10	Supplying of following 230/250 volts LED Flood light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Seperate housing for driver etc complete as per specification and P.A. should be greater than 0.9. LED chip efficacy ratio \geq 120 lumens /watt. 300 watt	2	Nos

म रि

टिशीत

शाखा

शाखा

शाखा

नस्ती प

लोक फे

टर 01

ग जान

(पी.डब्ल्यू)

का तैयार

11	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).	5.00	mtr
12	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as per specification. 30x20x15 cms.	1.00	Each
13	Supply of swaged steel tubular pole as per IS 2713 with base plate of size 300x300x6mm welded at bottom, necessary hole for cable entry and earthing stud welded at specified height including painting with one coat of red oxide zinc chromate primer. Designation 410 SP-53 height 11.00 metre	1.00	Each

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

Priya
उप अभियन्ता
नगर पालिक निगम, भिलाई