MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 39 के स्वीपर मोहल्ला सार्वजनिक शौचालय में सेप्टिक टेंक एवं अन्य संधारण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement: 1 fine sand) including testing of joints etc. complete: 100 mm diameter	20.00	m
2	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm2 in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	4	No.
3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floatingcoat of neat cement.	24	Sqm
4	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:	2.96	Cum
5	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design:100 mm diameter S.W. pipe	14	m
6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and		-
	applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	38	Kg
7	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	79.5	Kg
8	Providing and fixing sliding shutter with M.S. sheet 1 mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	42	Kg
9	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS: 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion etc complete.		-
	110 mm dia	28	M
	150 mm dia	28	M
10	Neat Cement punning.	31.5	Sqm
11	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	60.3	Sqm
12	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	1.4	Cum
13	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	5	Each
14	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	21	Sqm
15	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:		
	In Cement Mortar 1:5 (1 cement : 5 fine sand)	31.5	Sqn
16	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine cond)	56.7	Sqn
٠,	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.2	Cun

S.N.	PARTICULERS OF ITEMS	Quantity	UC
18	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856: 2000, complete.	9	Sqm
19	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe	2	Each
20	100 mm diameter and 1.20 m long complete as per standard design. Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	4.68	Cum
21	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	5.76	Sqm
22	Providing and fixing ceramic glazed wall tiles conforming to IS: \$5622 of approved make, colours, shades and 12 mm thick bed of cement Mortar 1:3cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	2.40	Sqm
23	Distempering with acrylic washable distemper to give an even shade. On old work (two or more coats)	96.00	Sqm
24	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	360.00	Sqm
25	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS: 7231, with all fittings and fixtures complete. White	5	Each
26	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS: 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required: White Orissa pattern W.C. pan of size 580x440 mm	2	Each
27	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS: 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required: White pedestal type	3.00	Each
28	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required: White Size 550x450 mm	2.00	Each
29	Towel rail (600mm long x 20mm dia)	2.00	P-
30	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, havingthermal stability for hot & cold water supply including all CPVC plain &brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.	2.00	Each
	15 mm nominal outer dia .Pipes.	20.00	
21	Providing and placing on terrace (at all levels) 1 and 23 mm nominal outer dia Pines	20.00	m m
31	and the base support for tools	500	Ltr
33	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:	8.00	No
]	Bib cock (250 grams)	8.00	No

	PARTICULERS OF ITEMS	Quantity	UOM
34	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	25.20	Cum
35	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.20	Cum
36	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	89.60	Sqm
37	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20mm nominal size)	10.76	Cum
38	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars.	968.40	Kg
39	Electrification Work (As electric SOR 01.06.2020 Lum-Sum)	10000.00	L-S

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer Municipal Corporation Bhilai