## MUNICIPAL CORPORATION OF BHILAI

वार्ड क्र. 49 श्रीराम चौक मैदान में पाईप लाईन व्यवस्था कार्य।

(As Per PWD Building SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
t	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	a) 50 mm dia. nominal bore	375.00	Metre
	b) 40 mm dia. nominal bore	400.00	Metre
	c) 25 mm dia. nominal bore	50.00	Metre
2	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):		
	a) 50mm. nominal bore.	7	Each
	b) 40 mm dia. nominal bore	7	Each
3	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete:		
	a) 50 mm nominal bore	5	Each
	b) 40 mm dia. nominal bore	8	Each
	c) 25 mm dia. nominal bore	5	Each
4	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	3	Each

Executive Engineer Municiapal Corporation Bhilai

Assistant Engineer Municipal Corporation Bhilai Sub Engineer
Municipal Corporation
Bhilai