## MUNICIPAL CORPORATION BHILAI NIT

WORK - जोन कं 05 अंतर्गत वार्ड कं. 70 हुडको में एम.आइ.जी—1 753 से 807 सी.सी नाली एवं स्लैब वर्क निर्माण कार्य।

PWD BUILDING SOR 01.01.20			
I/No.	Particular's Item	QTY	Oille
2	3	4	5
16.43.2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	2.26	Cum
1.26.3	Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba)As Per Item No. 01 Qty.	2.26	Cum
1.1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.  In all types of soils.	145.89	Cum
1.26.1	Carriage by mechanical transport upto 5 km lead: Earth As Per Item No. 03	145.89	Cum
3.1.2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm	15.04	
3.2.1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size) BOTTAM SLAB WALL TOP SLAB	38.12	Cum
3.12.	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo	1756.26	Kg
2.1	Providing and fixing form work including centring, shuttering, strutting staging, propping bracing etc. complete and including its removal at all level	433.20	Sqm

EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI

ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI

Sub Engineer

Municipal Corporation

Bhilai (C.G)