MUNICIPAL CORPORATION OF BHILAI

वार्ड क्र. 51 श.वी.ना. सिंह नगर चन्द्रमा चौक खुर्सीपार स्थित सार्वजनिक मंच एवं शेड निर्माण कार्य ।

S.N.	PARTICULERȘ OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	2.16	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	2.16	Cum
3	Steel work in tubular structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer. Electric resistance or induction butt welded tubes Grade-300	2250.00	Kg
4 5 F	Supply and fixing of precoated TILE PATTERN profile sheets of approved make, colour, over all size, corrugation shape and pitch, having total coated thickness (TCT) 0.45 mm (approx weight 4.9 kg/sqm) with Zn-Al coating and superior paint and having yeild strength of 550 MPa. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch excluding the cost of purlins, afters and trusses and including cutting to size and shape wherever required.	256.00	Sqm
П	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete nixer in all works upto plinth level xcluding cost of form work. 24:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40mm nominal size).	2.50	Cum
٠,	roviding and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water bsorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick ement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and	25.00	Sqm
P	ainting on new work (two or more coats) to give an even shade with:	50.00	Sqm
Pa pa of O	ainting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as er manufacturer's specifications to give protective and decorative finish including cleaning washing f surface etc. complete with: n new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	70.00	Sqm

Executive Engineer Municiapal Corporation Bhilai

Assistant Engineer Municipal Corporation Bhilai

Sub Engineer Municipal Corporation Bhilai