



## NIT.

## CONSTRUCTION OF SAMUDAYIK BHAWAN AT WARD 22 KURUD NEAR OF SARASWATI SHISHU MANDIR

	(AS PER BUILDING SOR 01.01.2015)		
S.NO	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose		
	including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from		
	the excavated area), including dressing and leveling of pits.		
	In all types of soil	37.07	CUM
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete		
	mixer in foundation, plinth and at ground level excluding cost of form work.		
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	20.05	CUM
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate		
	using concrete mixer in all works upto floor five level excluding cost of reinforcement and		
	form work.		,
	1:11/2:3 (1 cement : 11/2 coarse sand : 3 graded stone aggregate 20mm nominal size).	38.55	CUM
	Providing and placing in position reinforcement for R.C.C. work including straightening,		
	cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:		
	Thermo-Mechanically treated bars	3276.95	KG
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping		
	bracing etc. complete and including its removal at all levels, for:		
A	Foundations, footings, base of columns and plinth beam in any shape and size.	37.32	CUM
В	Columns, Pillars, Piers and likes- rectangular or square in shape	97.00	SQM
C	Beams, lintels, cantilevers & walls	59.34	SQM
D	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	116.65	SQM
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to		
	IS:12894-2002 of class designation 4.0 in foundation and plinth in:		
	Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	9.33	CUM
7	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1	,	
	cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including		
	formwork.		
		0.58	CUM
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to		
	IS:12894-2002 of class designation 4.0 in foundation and plinth in:		
	Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)Extra for brick work in uperstructure above	41.54	CUM
	plinth level for every floor or part thereof in addition to rate for foundation and plinth:		
9	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers		
	not exceeding 20cm in depth consolidating each deposited layer by ramming and watering,		
	including dressing etc. complete.		
		63.39	CUM
10	6mm thick cement plaster of mix:		
	In Cement mortar 1:4 (1 cement : 4 fine sand)	153.56	SQM
11	12mm thick cement plaster of mix:		
	In Cement Mortar 1:6 (1 cement : 6 fine sand)	307.27	SQM
12	15mm thick cement plaster on the rough side of single or half brick wall of mix:		~~1
	In Cement Mortar 1:6 (1 cement : 6 fine sand)	234.96	SQM
13	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars		- VIVI
13	welded to steel frame of windows etc. including applying a priming coat of red oxide zinc		
	O . I		
	chromate primer	1.0	

14	Providing and fixing steel door with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer		>
	printer.	638.25	KG
15	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.	300,20	
	Size 300x300mm	92.00	SQM
16	Providing and laying ceramic glazed floor tiles 300x300mm conforming to IS: 15622 of approved make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. In colours such as White, Ivory, Grey, Fume Red Brown,	72.00	S.V.
		14.00	SQM
17	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm		
		52.20	SQM
18	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:		
		4.95	CUM
1	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	350.72	0084
	0 W. H i. di ide di manium amulaian (alegtia) naint of required	350.72	SQM
	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.On new work (two or more coats)	207.01	0077
		287.96	SQM
2	Painting on new work (two or more coats) to give an even shade with:Premium synthetic enamel paint (2nd top most approved branded quality) to give an even shade.		
	I and the second se		1

ASSTT.ENGINEER Nagar Palik Nigam, Bhilai SUB ENGINEER Nagar Palik Nigam, Bhilai