



NAGAR PALIK NIGAM BHILAI

6

NIT

अधोसंरचना मद अंतर्गत वार्ड क्र.-15 अम्बेडकर नगर सड़क नं. 02 में सीमेंटीकरण कार्य।

(As per P.W.D ROAD S.O.R. W.E.F. 01.01.2015)

S.N.	PARTICULAR	QTY	UNIT
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	140.25	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads	46.75	cum
	P.C.C. M-15	184.88	cum
	P.C.C. M-30		
3	Transportation of metal i/c loading & unloading	105.19	cum
	For a lead upto 1 Km.		
			
	ASSTT. ENGINEER		
	Nagar Palik Nigam, Bhilai		
			
	SUB-ENGINEER		
	Nagar Palik Nigam, Bhilai		