


MUNICIPAL CORPORATION, BHILAI
N.I.T


(As per Road SOR wef- 01.01.2015)

Name Of Work - सेक्टर 9 बस्ती में विभिन्न गलीयों में सीमेंटीकरण कार्य।

S.No.	Details Of Item	Qty.	Unit
1	Excavation in Soil (by manual Means) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead up to 1000 meters as per relevant clauses of section 300	352.8	Cum.
2	Construction of granular sub-base by providing close graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve density, complete as per clause 401. (Page-15, Item-4.1)B By Mix in place method Disintegrated rock i.e. moorum having CBR value not less than 20 and P.I and L.L not more than 6 and 20 respectively.	352.8	Cum.
3	Construction of Shoulder (Construction of shoulders as per clause 407 with selected soil from borrow pits/ borrow areas having CBR not less than 12 and shall have L. L. and P.L. not more than 25% and 6% respectively, inclusive of all leads and lifts i/c clearing and scraping of existing surface, providing 4% camber compacting watering rolling and royalty charges etc. complete. With Smooth wheeled roller.	176.4	Cum.
4	Providing and laying C.C. for plain concrete/ reinforced concrete ice form work shuttering complete in as per drawing & as per specification etc. complete for concrete road (for village road). PCC M-30	352.8	Cum.
NON S.O.R ITEM			
A	Finishing Concrete pavements surface Using floater machine in all respects.	1764	Sqm


Executive Engineer
Nagar Palik Nigam Bhilai


Assi. Engineer
Nagar Palik Nigam Bhilai


Sub Engineer
Nagar Palik Nigam Bhilai