MUNICIPAL CORPORATION BHILAI

NIT

वार्ड क्र. 48 एवं 51 में स्थित सामुदायिक सह सार्वजनिक शौचालयों का संधारण कार्य। (कुल 07 नग)

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

SN.	Details of Item	Qty.	Unit
, 1	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS: 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal		
	expansion etc complete.	20.00	M
2	Neat Cement punning.	112.50	Sqm
3	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	63.00	Sqm
4	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:		
	In Cement Mortar 1:5 (1 cement : 5 fine sand)	44.10	Sqm
5	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	44.10	Sqm
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.51	Cum
7	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 100 mm diameter	35.00	m
8	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floatingcoat of neat cement. 40 mm thick	80.00	Sqm
	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design: 100 mm diameter S.W. pipe	30.00	m
10	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.		
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	140.00	Kg
11	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	294.00	Kg
12	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	367.50	Kg
13	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table -	12.60	Cum
14	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.12	Cum

	Details of Item	Qty.	Unit
. SN	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3	1.42	Cum
16	Coarse sand) but excluding reinforcement. Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	5.85	Cum
17	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	85.05	Kg
18	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	2.52	Cum
19	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS: 7231, with all fittings and fixtures complete. White	10	Each
20	Painting on old work (two or more coats) to give an even shade with: Satin synthetic enamel paint	147.00	Sqm
	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS: 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required: White Orissa pattern W.C. pan of size 580x440 mm	7	Each
2	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS: 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required: White pedestal type	7	Each
I S	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of tandard pattern, including painting of brackets, cutting and making good the walls wherever equired: White Size 550x450 mm	7	Eacl
Г	Fowel rail (600mm long x 20mm dia)	10	Eacl
& c c	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, havingthermal stability for hot cold water supply including all CPVC plain &brass threaded fittings i/c fixing the pipe with lamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent ement and the cost of cutting chases and making good the same including testing of joints complete s per direction of Engineer in Charge.		
+	15 mm nominal outer dia .Pipes.	40.00	m
- 	25 mm nominal outer dia .Pipes. Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:	40.00	m
_ E	Bib cock (250 grams)	45	No
c	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water bsorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick ement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement nd matching pigments etc. complete.	24.00	Sqn
t	Providing and laying ceramic glazed floor tiles conforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	11.52	Sqn
1-	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, hades and 12 mm thick bed of cement Mortar 1:3cement slurry @ 3.3kg per sqm including jointing in white cement mixed with matching pigment complete. Size upto 200x300mm	4.80	Sqn

SN.	Details of Item	Qty.	Unit
. 30	Distempering with washable distemper manufactured with the cow dung processing to give an even shade. On oldwork (two or more coats)	76.80	Sqm
31	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with th cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	360.00	Sqm
32	Add 5.00% extra for Electrification & Sanitary Work	16634.00	LS

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer

Municipal Corporation

Bhilai