

MUNICIPAL CORPORATION OF BHILAI NIT

वार्ड क्र. 40 छावनी चौक से तिरंगा चौक तक मुख्य मार्ग का सौदर्यीकरण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

ī	PARTICULERS OF ITEMS	QTY.	UNIT
	Supply of swaged steel tubular pole as per IS 2713 with base plate of size 300x300x6mm welded at bottom, necessary hole for cable entry and earthing stud welded at specified height including painting with one coat of red oxide zinc chromate primer. Designation 410 SP-26 height 9.00 metre	10	Each
	Erection of steel tubular pole or rail pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation & refilling etc as required of 7 metre to 10 metre	10	Each
3	Supply & fixing water tight terminal box made of 1.6 mm thick M S Sheet with detachable gland plate in bottom 4 way connector & 1 No. SPMCB inside the box for cable connection fixed to pole with 2 Nos. Clamp made from 40 x 3 mm MS flat with 2 Nos. nut bolts dully painted with 2 coat red oxide paint & 2 coat aluminum paint complete as required 30 x 20 x 15 cms	10	Each
4	Supply & Making end termination with brass compression gland & aluminum lugs for following size armored aluminum conductor power cable of 1.1 KV grade as required 3 x 25 sq.mm	20	Each
5	Supply & fixing & cramping suitable size & all type aluminum ferule/lugs for following size 1.1 KV grade power cable core/lead pressed with high pressure cramping tool including connection to switch gear/MCCB etc as required 25 sq.mm.	40	Each
6	Supply & Fixing GI Pipe Along With wall or pole/support with 2 nos. MS clamp for protection of underground cable in approved manner including bolts & nuts or metal dash fasteners complete as required 40 mm dia	80.00	Meter
7	Painting new steel & other metallic surface with red oxide zinc chromate primer paint complete with supply of material labour etc including preparation of surface	63.00	Sqm
8	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including baying MS triangular stiffner of size 150 X 50 X 5 mm thick, making arrangement for tightening the	10	Each
9	Painting wood steel & other metallic surface with aluminum paint complete with material & labour including preparation of surface	63.00	Sqm
10	Providing & Laying Cast In situ Cement Concrete 1:3:6 graded stone aggregate 40 mm nominal size	2.54	Cum
1		8.48	Cum
1:	as required	10	Set
1	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ concealed, steel/ PVC conduit/ PVC casing caping as required. 3 x 2.50 sq.mm	300.00	Sqm
1	Providing and fixing porcelain re-wireble fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). 32 amps	20	Each
	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 5 KV surge protection on pole bracket complete as required and furnishing 2 Yrs Guarantee certificate from manufacturer. 90 watt	12	Each
	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. 2 x 16 sq. mm	400.00	Meter

SN	PARTICULERS OF ITEMS	QTY.	UNIT
	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	192.00	Cum
18	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	400.00	Cum
19	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement mortar 1:6 (1 cement : 6 fine sand)	400.00	Cum
20	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1788.00	Kg
21	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc.complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	960.00	Cum
22	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	960.00	Cum

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai