

## MUNICIPAL CORPORATION OF BHILAI

वार्ड क्र. 43 बापू नगर में राजीव नगर पीपल पेड़ के समीप शेह निर्माण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	5.83	Com
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.  1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20mm nominal size).	5.83	Cam
3	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plant level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, which the bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming cost of red oxide zinc chromate primer.  Electric resistance or induction butt welded tubes Grade-250	3000.00	Kg
4	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 12/25m as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyetter top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet hall be fixed using self drilling /self tapping screws of size (5.5x. 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	750.00	Sqm
5	Painting on new work (two or more coats) to give an even shade with:	200.00	Sqm
6	Satin synthetic enamel paint  Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 120 lumens /watt.45 watt	6	Each
7	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.  2 x 16 sq. mm	20.00	metre

Executive Engineer

Municiapal Corporation

Bhilai

Assistant Engineer Municipal Corporation Bhilai Sub Engineer Municipal Corporation Bhilai