


# MUNICIPAL CORPORATION BHILAI

## NIT


कार्य का नाम :- वार्ड क्रमांक 54 सेक्टर 01 सड़क 13 में नाली संधारण कार्य।

As Per PWD Bullding SOR 01.01.2015


SN.	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	5.00	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	2.50	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	36.12	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	3.87	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.89	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	410.44	Kg
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	86.00	Sqm
8	Carriage by mechanical transport for 5 km lead. Earth	43.62	Cum



कार्यप्रमलन अभियन्ता  
नगर पालिक निगम, भिलाई



सहायक अभियन्ता  
नगर पालिक निगम, भिलाई



उप अभियन्ता  
नगर पालिक निगम, भिलाई