MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :— वार्ड—12 आर्य नगर स्थित लोधी भवन में मरम्मत एवं सौन्दर्यीकरण कार्य।

Pwd Building Sor 01.01.2015 & Electric Sor 01.06.2020

S.No.	Pwd Building Sor 01.01.2015 & Electric Sor 01.06			
	Description and details of work	Qty.	Unit	
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	6.00	Cum	
2	flooring or over roofs in cement/lime mortar including stacking of serviceable material and disposal of unserviceable material within 50 metro lead	36.00	Sqm	
3	the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :	42.00	Sqm	
4	square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete	50.00	Kg	
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	2.08	Sqm	
6	25mm thick Local RAJIM/ Red Flag stone slab in riser of steps, skirting, dado and pillars laid on 12mm (Average) thick cement mortar 1:4 (1 cement: 4 coarse sand) and joint with grey cement slurry mixed with pigments to match the shade of the slab i/c grinding, rubbing and polishing.	9.00	Sqm	
7	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.27	Cum	
8	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.	72.00	Sqm	
9	15mm thick Granite work (machine cut, table rubbed & mirror polished) for wall lining (veneer work) in cement mortar 1:3 (1 cement : 3 coarse sand) including pointing with cement mortar 1:2 (1 white cement: 2 marble dust) mixed with matching pigment. (Area of slab should be over 0.5 sqm). Granite stone black	4.24	Sqm	
10	Providing and making 12mm thick cement plaster of mix: In Cement Mortar	81.35	Sqm	
11	Providing and fixing ceramic glazed wall tiles conforming to 15: 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with	14.00	Sqm	
12	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: 20 mm dia. nominal bore	40.00	mtr.	
13	25 mm die nominal hara	50.00	mtr.	
14	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	4.00	Each	
15	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required: Soap dish plate	3.00	Each	

16	Tanval		
10	Towel rail (600mm long x 20mm dia)	3.00	Each
17	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side having 12 mm air gap including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. complete.	6.30	Sqm
18	Providing and applying plaster of paris putty over plastered wall surface including scaffolding complete Upto 2 mm thickness to make surface even and smooth in line and level.	1800.00	Sqm
19	Wall painting with premium emulsion (plastic)manufactured with cow dung processing emulsion paint of required shade to give e an even shade	1470.75	Sqm
20	Satin synthetic enamel point	32.76	Sqm
21	Providing and fixing "NETLON insect screens" with 25mm wide Hook and loop tape all around to wooden/ aluminium/ steel windows, ventilators and the like complete	12.00	Sqm
22	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	60.00	Sqm
23	Providing and fixing aluminium work for doors, windows, ventilators and made out of extruded aluminium standard sections (mainindows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neopreneweather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or holts. For fixed portion	50.00	Kg
24	provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately).	50.00	Kg
25	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	175.00	Kg
26	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with cow dung to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/10 sqm)	500.00	Sqm
27	Lettering with black Japan paint, per cm height.	1500.00	Per Latter
28	ADD EXTRA 5 % FOR ELECTRIFICATION	22720.00	Rs
29	ADD EXTRA 5 % FOR SANITORY	22720.00	Rs

Executive Engineer **Municipal Corporation** Bhilai (C.G)

Asstt. Engineer **Municipal Corporation** Bhilai (C.G)

Sub. Engineer **Municipal Corporatio** Bhilai (C.G)