MUNICIPAL CORPORATION OF BHILAI

वार्ड कं. 64 सड़क 6 एवं 7 के मध्य बैडमिंटन कोर्ट निर्माण कार्य।

		Quantity	UOM
	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling	6.00	cum
	of pits.(In all types of soils.) Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	3.00	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 1 coarse sand : 4 graded stone aggregate nominal	11.11	Cum
-	compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast	30.00	SQM
	interlock concrete blocks Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm	12.81	Cum
-	nominal size). Carriage by mechanical transport upto 5 km lead:	5.40	Cum
The Control of the Co	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and	6.90	SQM
	NON SOR Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass.Captivating design Vivacious colors Beautiful pattern.ColorGreen Material PPShape Straightls It Washable WashableThickness 25mm(B)	81.13	SQM

Asstt. Engineer Municipal Corporation Bhilai(C.G.)

Sul Engineer Municipal Corporation Bhilai(C.G.)

