

MUNICIPAL CORPORATION BHILAI
NH

कार्य का नाम :- वार्ड क्रमांक 55 सेक्टर 02, सड़क 02, सड़क 03, सड़क 04, सड़क
एवेन्यु बी में पुलिया संधारण कार्य।

As Per PWD Building SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead in cement mortar.	3.20	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead 1:3:6 or richer mix	11.52	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose including dressing and leveling of pits. In all types of soil.	38.40	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	3.84	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	17.92	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	1075.20	Kg
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	140.80	Sqm
8	Carriage by mechanical transport for 5 km lead. Earth	53.12	Cum

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई