

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- जोन क्रमांक 03 मदर टेरेसा नगर में वृक्षारोपण कार्य।

As Per PWD Building SOR 01.01.2015/ NON SOR ITEM

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	200.00	Cum
2	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	200.00	Cum
3	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately) : Holes 1.2 m dia and 1.2 m deep.	1500.00	each
NON SOR ITEM			
4	Providing and Planting of Kadam, Amaltash, gulmohar, Shisham, tapidya, Tikoma, Mallshrea, Pletra form, Karanj, Plam, Neem Etc Plant height up to 6'	1500.00	Each
5	Providing and fixing (Bamboo tree guard) Size of tree guard (2'X2'X6')	800.00	Each
6	Providing and fixing UV stablized Unplasticised Rigid PVC pipes (Single socketed) having 3.2mm wall thickness conforming to IS 13592(kg/sqm) 110mm	2000.00	Meter

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई