

MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


कार्य का नाम :- पार्षद निधि से वार्ड-08 कृष्णा नगर कुम्हार पारा, कृष्णा नगर सांस्कृतिक भवन का नईसुविधा अंतर्गत उन्नयन कार्य।


PwD Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	1.51	Cum
2	Applying cement slurry on R.C.C. slab or cement concrete work using 2.75 kg/ sqm for receiving cement concrete floor including roughening cleaning etc complete.	75.68	Sqm
3	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	5.28	Cum
4	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	52.80	Sqm
5	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	18.92	Sqm
6	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	11.88	Sqm
7	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	250.00	Sqm
8	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	100.00	Sqm
9	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	11.88	Sqm

10	Providing and fixing steel grid for false ceiling made from M.S. rectangular hollow tubes of 50x25x1.25mm (wall thickness) as main runners to be jointed to cross runners of same size by electric arc welding with spacing not exceeding 610x610mm in any direction. The frame to be screwed to the wall using wooden plugs and wood screws of size 50x8mm at an interval of not more than 300mm centre to centre. The grid to be supported using 6mm M.S. hanger bars at 1200mm centre to centre both ways bent, hooked, fixed to existing R.C.C. roof with fastner or to the truss as the case may be and bolted to the grid with the help of suitable M.S. holding cleats, complete.	100.00	Kg
11	Providing and fixing at all height false ceiling consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120 consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre IS: 2095- Part-I all complete as per drawing and specification and direction of the Engineer in Charge but excluding the cost of painting.	18.92	Sqm
12	Add 10% Electrification Chaggas	13160.00	Rs


Executive Engineer
Municipal Corporation
Bhilai (C.G)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G)


Sub. Engineer
Municipal Corporatio
Bhilai (C.G)