


MUNICIPAL CORPORATION OF BHILAI


NIT

कार्य का नाम :- वार्ड-66, सडक-18 मे छोटे उद्यान का निर्माण कार्य।

As per building sor 2015,

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	43.70	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	65.55	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 1 coarse sand : 4 graded stone aggregate nominal size).	437.00	Cum
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	65.55	Cum
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	39.33	Cum


Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)


Sub Engineer
Municipal Corporation
Bhilai(C.G.)