

MUNICIPAL CORPORATION, BHILAI

NIT

कार्य का नाम:- वार्ड क्रमांक 34 वीर शिवाजी नगर में जी.आई.पाईप लाईन
संधारण कार्य।

(As per P.W.D. Building S.O.R. W.E.F. 01.01.2015)

S.No.	Details of Item	UOM	Quantity
1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	Cum	6.00
2	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:	Cum	6.00
	40 mm dia. nominal bore	Meter	150.00
	32 mm dia. nominal bore	Meter	110.00
	25 mm dia. nominal bore	Meter	190.00
	20 mm dia. nominal bore	Meter	150.00
	15 mm dia. nominal bore	Meter	30.00
3	Providing and fixing 15mm nominal bore Brass bib/stop cock of approved quality : Bib cock (350gram)	Nos	10
4	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 32 mm nominal bore	Nos	2
5	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore	Nos	2
6	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end): 3=40 mm nominal bore	Nos	2

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई