



बाई 69 सेक्टर- 09 सड़क 28 काली मॉडल के समीप 01 नम को  
नन काम

ELEC SOR 2020 &amp; Building SOR 01.01.2015

	Description and details of work	Qty.	Unit
1	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by itable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level.All types of soil 150MM DIA	15.00	Rmt
2	Rocky strata including Boulder 150MM DIA	15.00	Rmt
3	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge, 150mm nominal size dia	15.00	Rmt
4	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of: 150mm nominal size dia	1.00	each
5	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete:		
	25 mm dia. nominal bore	35.00	Rmt
	50 mm dia. nominal bore	35.00	Rmt
6	Providing ISI Mark 32 mm dia G.I. ( B class) riser pipe and M. plunger rod in 3 meter length, socketed on one end as per IS: 1239 ( Part I) 1990 with up to date amendments and socket as per IS: 2062/1990 up to date amendment	15.00	Rmt
7	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.) below GB	25	cum
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	0.32	cum
9	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS 12894-2002 of class designation 4.0 in foundation and plinth in 7.5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)	2.24	Cum
10	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	1000.00	ltr
11	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: 19.13.1 Bib cock (250 grams)	15.00	each
12	19.12 Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required :		
a	19.12.2 20 mm nominal bore.	2.00	each
b	19.12.3 25 mm nominal bore.	2.00	each

13	19.14 Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:		
a	19.14.6 Stop cock (concealed) (600 grams)	2.00	each
b	19.15 Providing and fixing stainless steel drain jali of approved make/quality.	2.00	each
14	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
a	3.1.5 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.10	cum
15	12.3 Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 12.3.1 40 mm thick	6.00	sqm
16	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as required. 1.5.0 HP, single phase	1.00	Each
17	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as required. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set e) Ammeter 0-10 A 1 set	1.00	Each
18	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.	60.00	Metre

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai(C.G.)**

  
**Sub Engineer**  
**Municipal Corporation**  
**Bhilai (C.G.)**