

(6)

# MUNICIPAL CORPORATION BHILAI NIT

**कार्य का नाम :- वार्ड 54 सड़क 20-21 के मध्य नवीन मंच एवं  
सौंदर्यीकरण कार्य।**

Based on PWD/SOR 1-01-2015 (building works) Electrification Work 1.6.2020

Item No.	Particulars of item	Qty.	Rate
1	2	7	8
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	3	m <sup>3</sup>
2	Dismantling flag stone flooring laid in cement/lime mortar including stacking of serviceable material and disposal of unserviceable material within 50 metre lead.	25	Sqm
3	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	15	Sqm
4	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	0.3	m <sup>3</sup>
5	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	14.7	m <sup>3</sup>
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.8	m <sup>3</sup>
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	5	m <sup>3</sup>
8	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	3.56	m <sup>3</sup>



Item No.	Particulars of item	Qty.	Rate
1	2	7	8
9	Providing & placing in position cold twisted and hot rolled deformed steel reinforcement for RCC work I/c cutting, bending etc. complete as per drawing I/c cost of binding wire and I/c all wastage	284.8	kg
10	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) SOR Item No 7.5.4	2.00	m <sup>3</sup>
11	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) SOR Item No 7.5.4	2.00	m <sup>3</sup>
12	Providing & fixing of form work I/c centering ,shuttering ,strutting, staging ,Proping bracing etc. complete & removal upto 4 m height	1.92	sqm
13	Columns, Pillars, Piers and likes- rectangular or square in shape	3.2	m <sup>2</sup>
14	Weather shade, chhajja, Cornices and mouldings	4.5	m <sup>2</sup>
15	Providing and making 6mm thick cement plaster of mix:In Cement mortar 1:4 (1 cement : 4 fine sand)	25	m <sup>2</sup>
16	Providing and making 12mm thick cement plaster of mix In Cement Mortar 1:6 (1 cement : 6 fine sand)	80	m <sup>2</sup>
17	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:In Cement Mortar 1:6 (1 cement : 6 fine sand)	80	m <sup>2</sup>
18	Painting exterior surface with smooth exterior emulsion paint manufactured with the cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete	80.000	Sqm
19	providing and applying 2mm thick ready mix exterior grage putty (manufactured with cow dung processing ) on walls to make the surface smooth and even	105.00	sqm
20	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint. SOR Item No 14.22.1	68.51	
21	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	25	Sqm



Item No.	Particulars of item	Qty.	Rate
1	2	7	8
22	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer. SOR Item No .9.13	330.000	kg
23	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.	100.000	kg
24	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I.limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	25.000	KG
25	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer. Electric resistance or induction butt welded tubes Grade-250 Vertical tubular post 200 mm medium	950.000	KG
26	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm thick	25.000	Sqm
27	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. ( For Village roads) P.C.C. M-25	26.250	Sqm
	Beautification Work		



Item No.	Particulars of item	Qty.	Rate
1	2	7	8
28	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	200	sqm
29	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	12	Cum
30	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	40	Cum
31	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	20	Cum
32	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).	40	Cum
33	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	150	Each
	Furn like Arica, China etc (3 year old)	150	Each
34	Hibiscus (Flower)/ Rose	150	Each
35	Carpet grass (well developed)	25.00	sqm
36	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	40.00	Cum
37	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	40	Cum
38	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	400	sqm




Item No.	Particulars of item	Qty.	Rate
1	2	7	8
39	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.18	CUm
40	Carriage by mechanical transport upto 5 km lead:Earth	12	CUm
	<i>Tubular Pole(Electrical SOR 1.6.20)</i>		
41	Supply of swaged steel tubular pole as per IS 2713 with base plate of	5	Each
42	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement cor	5	Each
43	Supplying and fixing of single over hang (Arm) 1000 MM (long)x50 mm dia decorative GI street light pole bracket made out of GI "A" Class pipe welded to 300 MM Long GI Pole canopy of suitable dia at angle of 102.50 Degree including having GI triangular stiffner and making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy including FRP Dome on existing pole etc. as per enclosed drawing and as per direction of engineer-in-charge.For Street Light	5	Each
44	Supplying and fixing of double over hang (Arm) 1000 MM (long)x50 mm dia decorative GI street light pole bracket made out of GI "A" Class pipe welded to 300 MM Long GI Pole canopy of suitable dia at angle of 102.50 Degree including having GI triangular stiffner and making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy including FRP Dome on existing pole etc. as per enclosed drawing and as per direction of engineer-in-charge.	5	Each
45	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as per specification. 30 x 20 x 15 cms	5	Each
46	Supplying and making end termination with brass compression gland and aluminum lugs for following size armoured aluminum conductor power cable of 1.1 KV grade as per specification. 2 X 16 sq. mm (19 mm)	10	Each
47	Supplying, fixing and cramping suitable size and all type aluminium ferule/ lugs to following size 1.1 KV grade power cable core / lead, pressed with high pressure cramping tool including connection to switch gear/ MCCB etc as per specification. .25 sq. mm	30	Each



Item No.	Particulars of item	Qty.	Rate
1	2	7	8
48	Painting new steel and other metallic surface with red oxide zinc chromide primer paint complete with supply of material labour etc. including preparation of surface	54	Sqm
49	Painting wood steel and other metallic surface with Aluminium Paint complete with material and labour including preparation of surface.	54	Sqm
50	Providing timber / steel form work for cement concrete work at all levels including removing of the same.	14.13	Sqm
51	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as per specification and IS Code 3043: 1987(R 2016)	5	Set
52	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, multi strand wire in the existing surface/ concealed, FRLS PVC conduit / PVC casing capping as per specification and IS: 694 (2010) . 3 x 2.50 sq.mm	80	MTr
53	Providing and fixing porcelain re-wireble fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). 32 amps	5	Each
54	Supplying following DP MCB, 240 volts 6 amps to 32 amps 'C' curve	10	Each
55	Supplying, installation, testing and commissioning of following 230/250	5	Each
56	Supplying of following 230/250 volts LED Flood light fitting with all acc	3	Each
57	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 16 sq. mm	100	Meter
	Water Work Sanitary Work 2% As Per SOR Rate	1.00	JOB

कार्यपालन अभियन्ता  
नगर पालिक निगम, भिलाई

  
सहायक अभियन्ता  
नगर पालिक निगम, भिलाई

उप अभियन्ता  
नगर पालिक निगम, भिलाई