MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :— वार्ड क्रं. 35 आशादीप कॉलोनी, जनता स्कूल के पीछे एवं कमला गली में आर.सी.सी. नाली निर्माण कार्य।

As Per PWD Building SOR 01.01.2015

SN	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.		
	In cement mortar.	7.5	Cum
2	Demolishing cement concrete including disposal of material within 50 metre lead.		
	1:3:6 or richer mix	7.5	Cum
3	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.		
	and revening or plast in an appearance	232	Cum
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).		
		18.5	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	,	
		18.5	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
	graded stone aggregate zonim nominal sizzy.	65.91	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated		
K		3955	Kg
7	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: a)Foundations, footings; base of columns and plinth beam in any shape and size		
-	Situpe with a second of the se	557.4	Sqm
8	Carriage by mechanical transport for 5 km lead. Earth		
0		192.7	Cum

कार्यपालन अभियन्ता नगर पालिक निगम, भिलाई सहायके अभियन्ता नगर पालिक निगम, भिलाई

नगर पालिक निगम, भिलाई