

MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :- वार्ड 37 किसान चौक से उदिया मोहल्ला सी.सी. रोड एवं आर.सी.सी. वाली निर्माण कार्य।

(As Per PWD Building & Road SOR works w.e.f 01/01/2015)

SN.	Details of Item	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P C C M-25 Item Code 6.6 (III)	93.45	m ³
2	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	3.75	Cum
3	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	3.75	Cum
4	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose including dressing and leveling of pits. In all types of soil.	54.32	Cum
5	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	8.67	Cum
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	8.67	Cum
7	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	18.73	Cum
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	1003.8	Kg
9	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	234.4	Sqm
10	Carriage by mechanical transport for 5 km lead. Earth	55.64	Cum

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई