



**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**


कार्य का नाम :- वार्ड-03 मॉडल टाउन सड़क 03 एवं 05 में आर.सी.सी. नाली एवं पलिया निर्माण कार्य।

Pwd Building Sor 01.01.2015

| S.No. | Description and details of work  | Qty.    | Unit |
|-------|--|---------|------|
| 1     | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.  | 125.90  | Cum  |
| 2     | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 17.30   | Cum  |
| 3     | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3   | 40.63   | Cum  |
| 4     | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete.Thermo-Mechanically treated bars.                                | 4029.40 | KG   |
| 5     | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size              | 375.04  | Sqm  |
| 6     | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.     | 17.30   | Cum  |
| 7     | Carriage by mechanical transport for 5 km lead.  | 144.64  | Cum  |
| 8     | Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.   | 1.44    | Cum  |
| 9     | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.                                | 0.96    | Cum  |
| 10    | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).    | 4.14    | Cum  |
| 11    | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).   | 1.26    | Cum  |

  
**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)