


# MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


कार्य का नाम :- वार्ड-03 मॉडल टाउन में आंगनबाड़ी के पीछे पुलिया एवं नाली निर्माण कार्य।

PwD Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	68.20	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	9.40	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	22.04	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	2187.20	KG
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size	202.52	Sqm
6	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	9.40	Cum
7	Carriage by mechanical transport for 5 km lead.	78.32	Cum
8	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	0.72	Cum
9	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	0.48	Cum
10	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	2.07	Cum
11	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.63	Cum

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**