AS PER PWD BUILDING S.O.R 01.01.2015 UNIT RATE H/d QTY

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- वार्ड-09 पुड़की पारा में जर्जर पंप हाउस का नवीनीकरण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	4.32	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.14	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.16	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars	1116.00	Kg
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	5.40	Sqm
6	Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes	56.80	Sqm
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	7.44	Cum
8	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	0.06	Sqm
	Providing and making 6mm thick cement plaster of mix: n Cement mortar 1:4 (1 cement : 4 fine sand)	36.00	Sqm
	roviding and making 12mm thick cement plaster of mix: n Cement Mortar 1:6 (1 cement : 6 fine sand)	36.00	Sqm
11 P	roviding and making 15mm thick cement plaster on the rough side of ingle or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	36.00	Sqm
12 D	vistempering with acrylic washable distemper to give an even shade.0 on new work (Two or more coats)	72.00	Sqm
13 P	ainting exterior surface with PREMIUM ACRYLIC SMOOTH exterior aint of required shade as per manufacturer's specifications to give rotective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm ver and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	36.00	Sqm

			1
14	Painting on new work (two or more coats) to give an even shade with: Premium synthetic enamel paint	21.36	-3
15	Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	98.40	Sqm
16	Add Extra 5% For Electrification	11912.00	Rs

Executive Engineer Municipal Corporation Bhilai (C.G)

Asstt. Engineer **Municipal Corporation** Bhilai (C.G)

Municipal Corporatio Bhilai (C.G)