



MUNICIPAL CORPORATION OF BHILAI

NIT

भवन निर्माण कार्य हेतु।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	28.13	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.26	Cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	17.646	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	1764.60	Kg
5	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	28.92	Sqm
(B)	Columns, Pillars, Piers and likes- rectangular or square in shape	27.60	Sqm
(C)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	36.00	Sqm
(D)	Beams, lintels, cantilevers & walls	25.80	Sqm
6	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	36.00	Cum
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 + Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	17.86	Cum
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	0.56	Cum
9	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	38.08	Sqm
10	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	73.92	Sqm
11	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	74.82	Sqm
12	Providing and fixing flush door shutters, conforming to IS : 2202 (Part-1), decorative type core of block board construction with frame of first class hard wood and well matched teak ply veneering with vertical grains or cross bands and face veneers on both faces of shutters excluding hinges. 35 mm. thick (single leaf)	2.10	Sqm

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
13	Providing and fixing flush door shutters, conforming to IS : 2202 (Part-I), decorative type core of block board construction with frame of first class hard wood and well matched teak ply veneering with vertical grains or cross bands and face veneers on both faces of shutters excluding hinges. 25 mm. thick (double leaf for cupboard shutters with piano type hinges)		
14	Providing and fixing in position doors, windows and ventilators frames made of cold rolled pressed steel sheet framed profiles made from commercial M.S. Sheets conforming to I.S. 513 of 1973 and as per general specifications of I.S 4351 including hinges jamb, lock jamb, steel butt hinges, base tie, joints mitred and welded with 10cm long legs of size 15x3mm M.S. flat, embedded in cement concrete blocks 15x10x10cm size of grade M-10 or rawl plugs and screws or with fixing clips or with bolts and nuts including neatly compacted filling M-10 cement concrete in profile section applying a priming coat of red oxide zinc chromate primer. Single rebate/ mullion 80mmx50mm size, 1.6mm thick sheet	4.32	Sqm
15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	18.30	Metre
16	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	176.40	Kg
17	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	34.72	Sqm
18	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	74.82	Sqm
19	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	112.00	Sqm
		5.88	Sqm
<div style="display: flex; justify-content: space-between;"> <div style="text-align: center;">  ASSTT.ENGINEER Nagar Palik Nigam, Bhilai </div> <div style="text-align: center;">  SUB ENGINEER Nagar Palik Nigam, Bhilai </div> </div>			

NAGAR PALIK NIGAM BHILAI

NIT

बाउण्ड्रीवॉल निर्माण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including ...and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soils.	79.56	cum
2	Providing and laying nominal mix reinforcement cement concrete with .. excluding cost of reinforcement and form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		9.24	cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	31.77	cum
4	Providing and placing in position reinforcement for R.C.C. work .. including cost of binding wire all complete: Thermo-Mechanically treated bars	2700.45	kg
5	Providing and fixing formwork including centering,.. bracing etc. complete and including its removal at all levels, for:		
	Columns, Pillars, Piers and likes- rectangular or square in shape	71.30	sqm
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of..plinth in:Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	4.32	cum
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of..plinth in:Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)Extra for brick work in superstructure:Above plinth and upto floor five level.	32.40	cum
8	Steel work welded in built up sections/ framed work including cutting, .. priming coat of red oxide zinc chromate primer.		
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.		
	50 KG per sqm	760.00	kg
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).		
		1.16	cum
10	12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	464.00	cum
11	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:		
	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	464.00	sqm
12	Painting on new work (two or more coats) to give an even shade with:		
	Satin synthetic enamel paint	23.20	sqm
13	Lettering with black Japan paint, per cm height.		
		3000.00	per letter

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai

