



## MUNICIPAL CORPORATION BHILAI (C.G.)

कार्य का नाम :- वार्ड 07 अयप्पा नगर में सी.सी. रोड निर्माण कार्य।

### NIT

S.N	Description and details of work	No.	L	B	D	Qty.	Unit	Rate	Amount
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-10 (code 6.6 pg. 27)								
		1	300.00	4.50	0.10	135.00			
						135.00	cum		
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-30 (code 6.6 pg. 27)								
		1	300.00	4.50	0.20	270.00			
						270.00	cum		
3	Construction of Shoulders (Construction of shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting, watering rolling and royalty charges etc. complete (code 4.13 pg. 17)								
		2	300.00	0.60	0.20	72.00			
						72.00	cum		

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**