

# MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :- वार्ड-06 प्रियदर्शनी परिसर कोसानगर गौठान में बाउण्ड्रीवाल निर्माण कार्य।


Pwd Building Sor 01.01.2015


S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	72.9	Cum
2	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	9.18	Cum
3	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	3.60	Cum
4	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand) Extra for brick work in superstructure: Above plinth and upto floor five level.	29.16	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	23.040	Cum
6	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	4.500	Cum
7	Providing and placing in position reinforcement for P.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire etc. complete.	2003.50	
8	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.1111	



No.	Description and details of work	Qty.	Unit
9	Columns, Pillars, Piers and likes- rectangular or square in shape	75.000	Sqm
10	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	0.90	Cum
11	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	504.00	Sqm
12	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint with Cow dung of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work	504.00	Sqm

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**