



NAGAR PALIK NIGAM BHILAI NIT

जोन क्र.-02 वैशाली नगर क्षेत्रांतर्गत सीवर चेम्बर का ढक्कन संधारण कार्य।
(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.N	PARTICULAR	Q	U
1	Providing and laying nominal mix reinforcement cement concretereinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/ RCC work of any mix including form ...Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	29.40	cum
2	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	2940.00	kg
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;">  ASSTT.ENGINEER Nagar Palik Nigam, Bhilai </div> <div style="text-align: center;">  SUB ENGINEER Nagar Palik Nigam, Bhilai </div> </div>			