



NAGAR PALIK NIGAM BHILAI

NIT

जोन क्र.-02 वैशाली नगर कार्यालय में पार्किंग शेड संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including ..from the excavated area), including dressing and leveling of pits. In all types of soils.		
		7.50	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		1.80	cum
3	Structural steel work riveted or bolted or welded in built-up ections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.		
		1822.41	kg
4	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 .. rafters and trusses and including cutting to size and shape wherever required.		
		120.00	sqm
5	SS Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)		
		9.60	cum
6	15mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)		
		96.00	sqm
7	Painting on new work (two or more coats) to give an even shade with: Aluminium paint		
		130.00	sqm
8	Painting exterior surface with SMOOTH exterior emulsion paint of manufacturerd with cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (One or more coats applied @ 1.43 ltr/ 10 sqm)		
		140.00	sqm
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).		
		6.00	cum
10	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm thick		
		60.00	sqm
<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;">  ASSTT. ENGINEER Nagar Palik Nigam, Bhilai </div> <div style="text-align: center;">  SUB ENGINEER Nagar Palik Nigam, Bhilai </div> </div>			