

MUNICIPAL CORPORATION BHILAI

N.I.T.

कार्य का नाम :- पानी टंकियों की आवर्ती सफाई एवं पेयजल प्रदाय योजनाओं से संबंधित संरचनाओं में तड़ित चालक (Lightening Conductor) की स्थापना एवं निरीक्षण बाबत्।

| 1 | | UNIT | QTY |
|-----|---|-------|-----|
| 1 | Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe, with charcoal and salt as per specification and IS Code 3043, 1987 (R 2016) | Set | 14 |
| | Supplying and laying 25 mm X 5 mm copper strip at 0.50 metre below ground as strip earth electrode, including soldering, excavation and refilling the trench etc. as per specification. | Metre | 150 |
| . / | Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, copper tube, having single prong at top, with 85 mm dia 3 mm thick copper base plate having 4 nos holes for fixing etc. complete as per specification. | Each | 10 |
| - 1 | Making jointing of copper tape (with another copper tape, base of the finial or any other metallic object) by reverting, sweating and soldering/ nut bolting of as per specification. | Each | 200 |
| 1 | Providing and fixing copper tape 20 mm X 3 mm thick on parapet or surface of wall or lightning conductor complete as per specification.(For horizontal run) | Metre | 150 |
| r | Providing and fixing of lightning conductor finial, made of 25 mm dia 300 mm long, 6.1. tube, having single prong at top, with 85 mm dia 6 mm thick G.I. base plate laving 4 nos holes for fixing etc. complete as per specification. | Each | 4 |
| n | Making jointing of G.I. tape (with another G.I tape, base of the finial or any other netallic object) by reverting, sweating and soldering/ nut bolting of as per pecification. | Each | 80 |
| li | roviding and fixing G.I. tape 20 mm X.3 mm thick on parapet or surface of wall for ghtning conductor complete as per specification.(For horizontal run) | Metre | 80 |
| | roviding and fixing G.I. tape 20 mm X 3 mm thick on parapet or surface of wall for attning conductor complete as per specification.(For vertical run) | Metre | 60 |

Executive Engineer Municipal Corporation Bhilai

Asst. Epgineer **Municipal Corporation** Bhilai

Municipal Corporation Bhilai