

MUNICIPAL CORPORATION BHILAI

NIT

पार्षद निधि अंतर्गत वार्ड क्र. 43 बापू नगर में अंबेडकर भवन रोड़, शिव मंदिर रोड़ एवं तिवारी आटा चक्की लाईन में नाली निर्माण कार्य।

AS PER PWD BUILDING SOR 01.01.2015

SN.	Details of Item	Qty.	Unit
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 Meter lead. In cement mortar.	23.40	Cum
2	Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.	46.80	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	15.60	Cum
4	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	351.00	Sqm
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3	32.18	Sqm
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, bindinge as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	965.25	Kg
7	Carriage by mechanical transport for 5 km lead.	56.16	Cum

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai