



NAGAR PALIK NIGAM BHILAI NIT

विधायक निधि अंतर्गत वार्ड क्र.-16 रावण गाठा के पास दुर्गा मंदिर के पास छत्तयुक्त मंच निर्माण कार्य।

AS PER PWD BUILDING S.O.R 01.01.2015

SN	PARTICULAR	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or forupto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil	24.78	cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	8.80	cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	19.85	cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Cold twisted bar / Hot rolled deformed steel	1885.33	kg
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
5.a	Foundations, footings, base of columns and plinth beam in any shape and size.	30.80	sqm
5.b	Columns, Pillars, Piers and likes- rectangular or square in shape	71.00	sqm
5.c	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	130.58	sqm
5.d	Beams, lintels, cantilevers & walls	39.00	sqm
6	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	4.92	cum
7	super structure Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	4.36	cum
8	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	31.80	cum
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork	0.32	sqm
10	6 mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	90.32	sqm
11	12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	21.78	sqm
12	15mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	42.08	sqm
13	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and onforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	60.40	sqm

14	Distempering with acrylic washable distemper to give an even shade: on new work.(two or more coats)	50.00	sqm
15	Painting new exterior surface (two or more coats) with PREMIUM TEXTURED paint as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats)	50.00	sqm
<div style="display: flex; justify-content: space-between; align-items: flex-end;"> <div style="text-align: center;">  ASSTT.ENGINEER Nagar Palik Nigam, Bhilai </div> <div style="text-align: center;">  SUB ENGINEER Nagar Palik Nigam, Bhilai </div> </div>			