

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT

का नाम-वार्ड 63 सड़क 72 में स्थित उद्यान में प्रकाश व्यवस्था एवं संधारण कार्य  
(Based on PWD Building & Road SOR Wef from Dated 01-01-2015 Electrical SOR 2020)

S. No.	DESCRIPTION	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	8	9
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	3.75	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	0.75	cum
3	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	3.00	cum
4	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	140.00	sqm
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal	833.00	kg
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars	2.04	cum
7	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	163.20	kg
8	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	63.00	sqm
9	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	140.00	sqm
10	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:	500.00	litre
11	15 mm dia. nominal bore metre		
	20 mm dia. nominal bore	20.00	m
	25 mm dia. nominal bore	20.00	m
		20.00	m
12	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq cm Pigment Coloured (rubber mould) precast interlock concrete blocks	60.00	SQM
13	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio > 120 lumens /watt.60 watt	2.00	Each
14	Supplying following sizes FRLS PVC insulated , PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade and as per IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).3 x 16 sq. mm	25.00	mtr

Asstt. Engineer  
Municipal Corporation  
Bhilai(C.G.)

Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)

