


MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

का नाम- पार्स 63 लड्डू स्ट्रिड उद्यान - पे बालीवाल कोर्ट बिल्डिंग कार्प
As Per Building SOR 01.01.2015 & Non Sor Item

S.N.	Description and details of work	Qua.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	10.26	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	10.03	cum
3	providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam curtain wall in any shape and size and all type of all below plinth level.	6.00	sqm
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). @ Rs. 4073.00/m3	15.32	cum
5	Providing and fixing approved pipe hand rail by welding to iron railing including applying a priming coat of red oxide zinc chromate primer. M.S Pipe 50 mm dia	25.00	Kg
6	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete Aperture 50x50mm	40.00	sqm
7	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	80.00	SQM
NON SOR			
1	Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass.Captivating design Vivacious colors Beautiful pattern	80.00	sqm
2	LED MODULE 300watts (2year warranty) housing,blacksilver (bajab,havels etc.) AC90-350V,50/60HZ,PFC>0.95,100-135LM/W CRI>75,2700-6500K,IP67,427X305X122mm	6	No.
3	COSCO SPORTS Cotton (9.5 meter Volleyball Net COSCO SPORTSR (Cotton)	1	No.

Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)


Sub. Engineer
Municipal Corporation
Bhilai(C.G.)

