


**MUNICIPAL CORPORATION BHILAI (C.G.)****DETAILED ESTIMATE****NIT**

ग नाम - वार्ड 63 वार्ड के विभिन्न जगह में नाली पुलिया संधारण कार्य

	DESCRIPTION	QTY	UNIT
1	Demolishing cement concrete including disposal of material within 50 metre lead. 1:3:6 or richer mix	8.13	Cum
2	Carriage by mechanical transport upto 5 km lead: Dismantled Building debris (Mulba)	8.13	Cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	158.76	Cum
4	Carriage by mechanical transport upto 5 km lead: Earth	158.76	Cum
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	16.92	Cum
6,	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	51.27	Cum
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	2126	Kg
8	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	532.70	Sqm

**Asstt. Engineer**  
**Municipal Corporation**  
**Bhiali (C.G.)**

  
**Sub-Engineer**  
**Municipal Corporation**  
**Bhiali (C.G.)**