

MUNICIPAL CORPORATION OF BHILAI NIT


कार्य का नाम :-वार्ड कं. 59 सेक्टर 5 सड़क एनपीए के समीप यात्री प्रतिकालय निर्माण कार्य।

The Estimate Is Prepared as per S.O.R of P.W.D (Building works) w.e.f. 01-01-2015

S.N	N	PARTICULARS	QTY	UNIT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/height including disposal of rubbish upto 1.5 m lift and lead upto 50 m (at least 5m away from the dressed area).	160.00	SQM
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	16.90	CUM
3	1.6	Extra for every additional lift of 1.5M or part there of All types of soil	4.06	CUM
4	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm. In depth consolidation each deposited layer by ramming and watering with a lead upto 50M. And lift upto 1.5M.	12.68	CUM
5	1.18	Providing and filling in plinth with sand /crusher dust and hard moorum under floor in layers not exceeding 20 cm in depth and consolidating each deposited layer by ramming and watering, including dressing etc. complete.	20.42	CUM
6	3.2.1	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	7.07	CUM
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: 3.1 2.1 Thermo-Mechanically treated bars FE 41 5	707.20	KG
8	2.1	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: 2.1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	24.50	SQM
9	7.5.4	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to 15:12894-2002 of class designation 40 in foundation and plinth in: 7.5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand) - Extra for brick work in superstructure Above 1 plinth level for every floor or part thereof in addition to rate for foundation and plinth:	0.54	CUM
10	9.3.2	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.	1706.00	KG
11	10.11	Supply and fixing of pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	75.00	SQM
12	10.9	Providing and fixing 15 cm. wide 45cm. overall semi circular plain G.I. sheet gutter with iron brackets 40x3 mm size, bolts, nuts and washers etc. including making necessary connections with rain water pipe complete as per designs.	15.00	MTR

13		Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturers specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more	50.00	SQM
14	pwd Road SoR 8.7	Overhead Signs (Providing and erecting overhead signs with a corrosion resistant aluminum alloy sheet reflectorized with high intensity retro-reflective sheeting of Micro prismatic grade type with vertical and lateral clearance given in clause 802.2 and 802.3 and installed as per clause 802.6 over a designed support system of aluminum alloy or galvanized steel trestles and trusses of sections and type as per structural design requirements and approved plans Aluminium alloy plate for overhead sign	23.40	SQM
15	9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete	222.88	KG
16	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. Size 600x600mm	30.00	SQM

सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई