


MUNICIPAL CORPORATION BHILAI (C.G.)
NIT


का नाम :- वार्ड क्र. 01 जुनवानी से खम्हरिया रोड में बस स्टाप निर्माण कार्य।

PwD Building Sor 01.01.2015

	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. 1.1.1 In all types of soils.	1.84	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.58	cum
3	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in: 7.4.1 Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	2.76	cum
4	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	1.38	cum
5	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	9.45	cum
6	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	6.90	sqm
7	Providing and replacing broken floor tile with ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including removing the broken tile and mortar, pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	31.50	sqm
8	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete. SS Grade 304	950.00	kg
9	Overhead signs(provind and erecting overhead signs....) aluminum alloy plate for over head sign	4.20	sqm


Executive Engineer
Municipal Corporation
Bhilai (C.G.)


Asstt. Engineer
Municipal Corporation
Bhilai (C.G.)


Sub. Engineer
Municipal Corporation
Bhilai (C.G.)