

MUNICIPAL CORPORATION OF BHILAI

NIT


वार्ड 45 बालाजी नगर एनएवी सड़क का सीमेंटीकरण कार्य।

(As Per PWD Building/Road SOR 01.01.2015)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	537.50	Sqm
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)		
	P.C.C. M-10	53.75	Cum
	P.C.C. M-25	80.63	Cum

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai