

**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**

कार्य का नाम :- वार्ड-04 नेहरू नगर पूर्व एवं पश्चिम में नाली निर्माण कार्य।

Pwd Building Sor 01.01.2015

| S.No. | Description and details of work  | Qty.    | Unit |
|-------|--|---------|------|
| 1     | Excavation for all types and the sizes of foundation, trenches and drains or for any other purpose Including dressing and leveling of pits. In all types of soil.  | 44.00   | Cum  |
| 2     | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size) | 13.20   | Cum  |
| 3     | Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a) Foundations, footings; base of columns and plinth beam in any shape and size             | 572.00  | Sqm  |
| 4     | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:1.5:3  | 52.80   | Cum  |
| 5     | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.                               | 2640.00 | KG   |
| 6     | Carriage by mechanical transport for 5 km lead.  | 74.80   | Cum  |

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**