

MUNICIPAL CORPORATION OF BHILAI


NIT

वार्ड क्र. 48 बी.एस.पी. क्वार्टर के पास पाईप लाईन विस्तारीकरण, उड़िया बस्ती में सार्वजनिक मंच का संधारण एवं अन्य व्यवस्थाएं।

(As Per PWD Building SOR 01.01.2015, Electrical SOR 01.06.2020 & NON SOR ITEM)

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	1.68	Cum
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	14.74	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.76	Cum
4	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1:3 (1 cement : 1 coarse sand : 3 graded stone aggregate 20mm nominal size).	9.026	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	902.60	Kg
6	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
(A)	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	13.08	Sqm
(B)	Columns, Pillars, Piers and likes- rectangular or square in shape	13.20	Sqm
(C)	Beams, lintels, cantilevers & walls	5.52	Sqm
(D)	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	29.48	Sqm
7	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	6.60	Cum
8	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.38	Cum
9	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	1.98	Cum
10	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	21.20	Sqm
11	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	9.90	Sqm
12	Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)	9.90	Sqm
13	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	15.00	Sqm
14	Painting exterior surface with SMOOTH exterior emulsion paint manufactured with the cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with : On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over)	9.90	Sqm
15	Wall painting with premium emulsion (plastic) manufactured with the cow dung processing emulsion paint of required shade to give an even shade. On new work (two or more coats)	21.20	Sqm

S.N.	PARTICULARS OF ITEMS	Quantity	UOM - 2020)
16	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete. SS Grade 304	190.00	Kg
17	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
a	50 mm dia. nominal bore	300.00	Metre
b	40 mm dia. nominal bore	250.00	Metre
c	25 mm dia. nominal bore	210.00	Metre
d	15 mm dia. nominal bore	100.00	Metre
18	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):		
a	50 mm dia. nominal bore	25	Each
b	40 mm dia. nominal bore	20	Each
c	25 mm dia. nominal bore	20	Each
19	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete:		
a	50 mm dia. nominal bore	20	Each
b	40 mm dia. nominal bore	20	Each
c	25 mm dia. nominal bore	20	Each
20	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	60	Each
21	Add Extra For Electrification work (As per SOR)	39608.00	LS
22	NON SOR ITEM Providing & fixing of Steel Bench Area 1.20x0.70 m Height 0.45 m above level seating ----- proper grip fixing with 1:2:4 Cement Concrete	10	Each


Executive Engineer
 Municipal Corporation
 Bhilai

Assistant Engineer
 Municipal Corporation
 Bhilai


Sub Engineer
 Municipal Corporation
 Bhilai